ENGINEERING DEPARTMENT

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated 22nd February 1939.

The attention of the public is invited to the detailed notification, calling for tenders for taking over the lease of the shops attached to the Central Police Station at Dodpet, Mysore (Hamilton Building), published on page 403 of Part VI of the *Mysore Gazette*, dated 2nd March 1939.

Each tender must be accompanied by an earnest money of Rs. 50.

The last date for receiving the tender is 15th March 1939, at 3 P.M.

M. A. RAMANUJAM,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated 17th February 1939.

The attention of the public is invited to the Gazette Notification, dated the 17th February 1939, *vide* pages 352-354, Part VI of the *Mysore Gazette*, dated 23rd February 1939, calling for tenders for restoring Doddagaddavalli Hirekere, Salagame Hobli, Hassan Taluk and the last date for the receipt of the tender is 13th March 1939.

Abstract Notification dated 25th February 1939.

The attention of the public is invited to the notification, in the *Gazette*, dated the 2nd March 1939, *vide* pages 404-406, calling for tenders for restoring Konkere Oormundinakere of Arsikere Taluk. and the last date for the receipt of tenders is 20th March 1939.

Abstract Notification dated 25th February 1939.

The attention of the public is invited to the notification in the *Gazette*, dated 2nd March 1939, *vide* pages 406-409 calling for tenders for constructing "Local Fund Dispensary at Rudrapatna, Arkalgud Taluk," and the last date for receipt of tender is 25th March 1939.

Notification dated 25th February 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 25th March 1939 for widening the super-passage at 20/24th mile of Kattepur Channel.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for widening the super-passage at 20/24th mile of Kattepur Channel." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 300 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract (cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the 5 per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Executive Engineer, Hassan Division, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents, in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member therefor or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of December 1939, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer shall be final and legally binding.

18. The earnest money for rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers for the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will be however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgements of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for widening the super-passage at 20–24th mile of Kattepur Channel.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation in all soils	C.yd.	0 4 0	493	
2	Stone jelly concrete in surki mortar for foundation	C.ft.	0 4 0	1,564	
3	Surki concrete mixed with small proportion of cement	,,	0 5 0	1,825	
4	Size stone in surki mortar for superstructure ..	,,	0 5 0	7,285	
5	Burnt brick in surki mortar	,,	0 4 6	4,292	
6	Burnt stone slabs 6" thick dressed and fixed in cement mortar	S.ft.	0 7 0	1,092	
7	Cement concrete slab (1 : 2 : 4) 3" thick	C.ft.	1 0 0	124	
8	Rough stone apron 2 ft. thick for the flooring with jelly wedging, etc., complete	C.yd.	1 8 0	291	
9	Cement pointing to size stones in surki mortar ..	Sqr.	4 0 0	27·17	
10	Cement plastering to brick walls	Sqr.	7 0 0	34·82	
11	Dismantling the existing left wall	C.ft.	0 0 3	1,744	
12	Dismantling stone structure	,,	0 0 4	2	

Notification dated 27th February 1939.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 27th March 1939, for constructing a new tank at Gangur, Belur Taluk.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as " Tender for constructing a new tank at Gangur, Belur Taluk."

The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 1,950 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender, an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the P. W. D. Current Schedule of Rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Hassan Division, Hassan, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the P. W. D. by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 500 which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Hassan Division, Hassan.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental Officers will be, however, considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractors should arrange for the payment of royalty and tolls.

Abstract estimate for construction of a new tank at Gangur, Belur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund at R. L. 84·50.		Rs. a. p.		Rs.
1	Clearing jungle, etc.	Grade	15 0 0	19	
2	Clearing seat of bund and using to rear half	C.yd.	0 4 0	4,608	
3	Cutting longitudinal grips, etc.	Grade	10 0 0	16	
4	Excavating puddle trench	C.yd.	0 4 0	1,339	
5	Do foundation to revetment	,,	0 4 0	2,276	
6	Do do corewall	,,	0 6 0	91	
7	Benching rock	L. S.	..	..	25
8	Stone jelly concrete in surki mortar	C.ft.	0 4 6	968	
9	Burnt stone in surki mortar core wall	,,	0 6 0	3,208	
10	Clay puddle wall with gravel mixtures (1 : 5)	C.yd.	0 8 0	5,923	
11	Earthwork to bund using suitable soil including watering and tamping with lead, lift, etc., and gravel mixture 1 : 4	,,	0 5 0	49,312	
12	New stone revetment	,,	1 8 0	5,286	
13	Gravel backing	,,	0 8 0	1,918	
14	Turfing with Garike or Mani turf	Sq.yd.	0 1 0	8,028	
15	Grade stones fixing, complete	Each	2 0 0	19	
16	Providing and fixing Index stones	,,	1 4 0	19	
17	Survey and Constructive Detail stone	,,	50 0 0	50	
18	Bench mark stones	,,	4 0 0	2	
19	Gauge stones	,,	15 0 0	3	
	Sluice No. 1 at 66·00.				
1	Earthwork excavation	C.yd.	0 5 0	90	
2	Surki concrete	C.ft.	0 4 6	500	
3	Burnt brick in surki mortar	,,	0 6 0	1,374	
4	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 12 0	340	
5	Surki mortar plastering	Sqr.	5 0 0	3.00	
6	Cement plastering	,,	12 0 0	1.23	
7	Cement pointing	L. S.	..	..	10
8	Providing Teakwood plug and rod with locking arrangement	,,	..	..	35
9	Cutting orifice, etc.	,,	..	..	7
	Sluice No. 2. Low level R. L. 61·00.				
1	Earthwork excavation	C.yd.	0 5 0	98	
2	Surki concrete	C.ft.	0 4 6	643	
3	Burnt brick in surki mortar	,,	0 6 0	1,516	
4	Burnt stone slabs 6″ thick dressed and fixed	Sq.ft.	0 12 0	430	
5	Surki mortar plastering	Sqr.	5 0 0	3.00	
6	Cement plastering	Sqr.	12 0 0	1.77	
7	Cement pointing	L. S.	..	..	10
8	Providing teakwood plug, rod, etc.	,,	..	..	35
9	Cutting orifice, etc.	,,	..	..	5
	Waste weir 200 ft. Right R. L. 79·00.				
1	Earthwork	C.yd.	0 5 0	3,591	
2	Surki concrete	C.ft.	0 4 6	975	
3	Burnt brick in surki mortar	,,	0 6 0	2,969	
4	Burnt stone slabs 6″ thick dressed and fixed	Sq.ft.	0 12 0	344	
5	Surki plastering	Sqr.	5 0 0	2.00	
6	Rough stone work	C.yd.	1 8 0	3	
7	Turfing	L. S.	..	..	9
8	Providing clamps, etc.	,,	..	..	40
	Distribution.				
1	Excavating sluice channel	C.yd.	as per nature of soil		L. S. 650
2	Constructing Relieving weir	R.ft.	3 0 0	140	

P. SUBBA RAO,
Executive Engineer.
6 c